



PLAN





1250/1500 GALLON 2 COMPARTMENT SEPTIC TANK NOT TO SCALE

- CENTER-TO-CENTER TRENCH SPACING = 12 FEET


- INSTALL INFILTRATORS ACCORDING TO

INSTRUCTIONS

MANUFACTURER'S CURRENT INSTALLATION

EROSION & SEDIMENT CONTROL NOTES:

- ALL EROSION & SEDIMENT CONTROL MEASURES TO BE CONSTRUCTED AS DETAILED AND SPECIFIED IN THE CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL JANUARY 2002 AS AMENDED.
- ALL EROSION & SEDIMENT CONTROL MEASURES SHALL BE INSTALLED PRIOR TO ANY CONSTRUCTION, PROPERLY MAINTAINED DURING CONSTRUCTION AND REMAIN IN PLACE UNTIL ALL DISTURBED AREAS HAVE BEEN PROPERLY STABILIZED. AFTER INSTALLATION OF THE INITIALLY PRESCRIBED MEASURES, ADDITIONAL MEASURES MAY BE REQUIRED TO ADDRESS FIELD CONDITIONS AS ORDERED BY THE TOWN OF ANDOVER OR ITS DESIGNATED AGENT(S).
- THE SMALLEST PRACTICAL AREA OF LAND SHOULD BE EXPOSED. THE EXPOSURE SHOULD BE THE SHORTEST PERIOD OF TIME. WHEN NECESSARY TEMPORARY VEGETATION AND OR MULCHING SHOULD BE USED TO PROTECT EXPOSED AREAS. FINAL VEGETATION SHOULD BE INSTALLED AS SOON AS POSSIBLE. WHEREVER FEASIBLE NATURAL VEGETATION SHOULD BE RETAINED AND PROTECTED.
- THE STOCKPILING OF BUILDING MATERIALS SHALL BE WITHIN THE AREA OF DISTURBANCE.
- SEEDBED PREPARATION: FINE GRADE AND RAKE SOIL TO REMOVE ANY STONES LARGER THAN 2 INCHES. INSTALL ANY NEEDED EROSION CONTROL DEVICES SUCH AS SURFACE WATER DIVERSIONS. APPLY LIMESTONE AT A RATE OF TWO TONS PER ACRE OR 90 POUNDS PER 1000 SQUARE FEET. FERTILIZE WITH 10-10-10 AT A RATE OF 11 POUNDS PER 100 SQUARE FEET. WORK LIME AND FERTILIZER INTO THE SOIL TO A DEPTH OF FOUR INCHES.
- SEED APPLICATION: APPLY SHADE TOLERANT GRASS MIXTURE BY HAND, CYCLONE SEEDER OR HYDROSEEDER. SEEDING SHALL BE DONE BETWEEN APRIL 1 AND JUNE 1 OR BETWEEN AUGUST 15 AND SEPTEMBER 1. IF SEEDING CANNOT BE DONE DURING THESE TIMES, REPEAT MULCHING PROCEDURE UNTIL SEED CAN BE DONE.
- ESTABLISH PERMANENT VEGETATION USING A SEED MIXTURE OF: KENTUCKY BLUEGRASS 20 LBS/ACRE CREEPING RED FESCUE 20 LBS/ACRE PERENNIAL RYE GRASS 5 LBS/ACRE 45 LBS/ACRE THE RECOMMENDED DATES FOR SEEDING ARE APRIL 1 THROUGH JUNE 1 AND AUGUST 15 THROUGH SEPTEMBER 1.
- MULCHING: IMMEDIATELY FOLLOWING SEEDING, MULCH THE SEEDED SURFACE WITH STRAW OR HAY AT A RATE OF 1.5 TO 2 TONS PER ACRE. MULCH SHALL BE SPREAD BY HAND OR WITH A MULCH BLOWER. PUNCH MULCH INTO SOIL SURFACE APPROXIMATELY TWO TO THREE INCHES.




* NOTE: 2" BIT. CONCRETE PAVEMENT REQUIRED WHERE SLOPE EXCEEEDS 10%


DRIVEWAY INSTALLATION DETAIL

NOT TO SCALE

DOUBLE INFILTRATOR QUICK 4 STANDARD (NOT TO SCALE) MOUND FOR PROPER DRAINAGE **ESTABLISH VEGETATIVE COVER** · NATIVE BACKFILL 12" MIN. H-10 LOADING 6" MIN., NON-TRAFFIC AREAS FILTER FABRIC NO. 4 (1 1/4") STONE AGGREGATE OR, NO. 6 (3/4") STONE AGGREGATE - EFFECTIVE LEACHING AREA = 5.9 SQ FT/LF

DETAIL





SILT FENCE DETAIL (NOT TO SCALE)

DESIGN NOTES:

- ALL CONSTRUCTION TO CONFORM TO STANDARDS OF THE CONNECTICUT PUBLIC HEALTH CODE AND TO THE SATISFACTION OF THE TOWN SANITARIAN
- PERCOLATION RATE FOR DESIGN: 10 min./inch **DEPTH TO RESTRICTIVE LAYER: 25"**
- REQUIRED LEACHING AREA FOR 4 BEDROOM BUILDING = 577.5 SF ELA
- DESIGN: USE 100 LF OF 12" HIGH DOUBLE INFILTRATOR UNITS ELA PROVIDED = 5.9 SF/LF x 100 LF = 590 SF ELA
- THIS SYSTEM HAS NOT BEEN DESIGNED FOR THE USE OF LARGE CAPACITY (+100 GALLONS), DISCHARGE TYPE BATHTUBS. RESIDENTIAL GARBAGE DISPOSALS ARE NOT ANTICIPATED FOR THIS DESIGN. IN THE EVENT THAT SUCH AN INSTALLATION IS CONTEMPLATED FOR THE PROPOSED HOUSE, A LARGER SEPTIC TANK AND INCREASED LEACHING FIELD CAPACITY WILL BE REQUIRED.
- THE DESIGN SHOWN HEREON CONFORMS TO ALL APPLICABLE STATE AND LOCAL HEALTH CODE REQUIREMENTS AND TO GOOD ENGINEERING PRACTICE. I CAN NOT GUARANTEE AGAINST FAILURE DUE TO IMPROPER INSTALLATION, IMPROPER MAINTENANCE OR TO NATURAL PHENOMENA BEYOND THE SCOPE OF NORMAL FIELD INVESTIGATION.

SEPTIC SYSTEM CONSTRUCTION NOTES:

- 1. CONSTRUCTION SEQUENCE
 - A. STRIP & STOCKPILE TOPSOIL FROM LEACHING AREA. B. CONSTRUCT LEACHING UNITS TO DESIGN LINE & GRADE.
- D. LOAM, FINE GRADE TO FINISHED GRADE AND SEED. PROTECT DISTURBED AREAS
- WITH EROSION CONTROLS UNTIL FIRST MOWING.
- THE PIPE BETWEEN THE HOUSE AND SEPTIC TANK SHALL BE 4 IN. EXTRA HEAVY CAST IRON, DUCTILE IRON OR EXTRA STRENGTH PVC ASTM D1785 SCHD 40 OR APPROVED EQUAL.
- 3. ALL DISTRIBUTION PIPE IS TO BE ASTM D3034 SDR 35 (4"PVC) OR APPROVED EQUAL UNLESS NOTED.
- 4. SEPTIC TANK SHALL BE SET LEVEL ON A MINIMUM OF 6" OF PROCESSED GRAVEL OR BROKEN STONE ON
- 5. THERE ARE NO APPARENT WELLS OR SEPTIC FIELDS WITHIN 75' OF THE PROPOSED WELL AND SEPTIC SYSTEM
- APPROVED STONE AGGREGATE FOR LEACHING TRENCHES SHALL BROKEN STONE, CRUSHED STONE, OR SCREENED GRAVEL MEETING CT DOT FROM 814A SPECIFICATION FOR M.01.01 FOR NO. 4 STONE:

SIEVE SIZE	PERCENT PASSING (BY WEIGHT)
2-INCH	100
1-1/2-INCH	90-100
1-INCH	20-55
3/4-INCH	0-10
3/8-INCH	0-5


- 0-3 0-1.5
- THE DEPTH OF THE LEACHING UNITS SHALL NOT EXCEED 7" INTO ORIGINAL GRADE.
- 8. THE LOCATION AND ELEVATION OF THE PROPOSED SEPTIC SYSTEM SHALL BE STAKED IN THE FIELD BY A LICENSED LAND SURVEYOR. BENCHMARK TO BE SET IN THE VICINITY OF THE LEACH FIELD AT THE TIME OF

LEACHING SYSTEM CONSTRUCTION NOTES:

- 1. TOPSOIL TO BE STRIPPED OFF PRIOR TO FILLING. FILL MATERIAL BETWEEN AND BEYOND TRENCHES TO BE PERVIOUS, GOOD QUALITY AND CLEAN MEDIUM SAND (SELECT FILL) PLACED AND COMPACTED IN 6" LIFTS. SELECT FILL SHALL MEET THE FOLLOWING MINIMUM REQUIREMENTS:
- A. THE FILL SHALL NOT CONTAIN ANY MATERIAL LARGER THAN 3 INCHES. B. THE FILL SHALL NOT CONTAIN MORE THAN 45 PERCENT GRAVEL (GRAVEL IS BETWEEN NO. 4 & 3" SIEVES) NO MORE THAN 45 PERCENT OF THE MATERIAL CAN BE RETAINED ON THE NO. 4 SIEVE.
- % PASSING: WET SEIVE 100 70-100 **10-50 0-20 0-5


C. THE FILL LESS THE GRAVEL SHALL MEET THE FOLLOWING GRADATION CRITERIA:

- % PASSING: DRY SEIVE 100 70-100 10-75 0-5 0-2.5
- ** PERCENT PASSING THE #40 SIEVE CAN BE INCREASED TO NO GREATER THAN 75% IF THE PERCENT PASSING THE #100 SIEVE DOES NOT EXCEED 10% AND THE #200 SIEVE DOES NOT EXCEED 5%.
- 2. DOCUMENTATION OF TEST RESULTS ARE TO BE PROVIDED TO THE HEALTH DISTRICT.
- 3. FILL MATERIAL TO BE PLACED PRIOR TO TRENCH EXCAVATION. NO TRAFFIC OTHER THAN TRACK-DRIVEN EQUIPMENT IS TO CROSS, DUMP, UNLOAD OR OTHERWISE COMPACT THE FILL AREA AFTER TOPSOIL REMOVAL. FILL MATERIAL TO BE DUMPED AT THE EDGE OF THE STRIPPED AREA AND SPREAD AND COMPACTED WITH TRACK-DRIVEN VEHICLES. STOCKPILING IS TO TAKE PLACE UPGRADIENT OF THE LEACHING AREA. THE AREA DOWN GRADIENT OF THE LEACHING AREA IS NOT TO BE DISTURBED.



ANTI – TRACKING PAD DETAII

NOT TO SCALE



0

OB ND