

IWWC #23-05 – 17 School Road (Town of Andover)
Reconstruction and associated tree removal for improved community garden
Submitted 05-09-2023

Project Description

- Approximately .15 acres of trees will be removed to provide full sun for the community garden. Stumps will be removed and area will be graded and seeded.
- Sand and gravel will be used as fill underneath the proposed garden, which will be approximately 75-feet by 33-feet.
- Topsoil will be placed on top of sand and gravel base.
- Garden boxes will be constructed with wood timbers as frames.
- A mulch berm will be used as erosion control to protect wetlands from any erosion caused by tree removal and fill placed for garden.
- Disturbed areas will be seeded after completion of fill placement and grading.
- Existing topsoil pile (marked on site drawing submitted on 05-09-2023) will be removed, or will be used as topsoil for community garden. Area will be seeded and stabilized after topsoil pile has been removed.
- A wooded buffer will remain between wetlands and area of clearing.